

Questions received 2.12.2024

Question:

What is the proposed time frame for construction?

Answer:

Completion by May 24, 2024 (Labor Day Weekend)

Question:

Does the order of repairs matter? Is an inspection required to be the first item? And will a final survey be needed for all under water work?

Answer:

Order of repairs does not matter. Yes, an inspection is required to be the first item. A final survey is not necessary, but a diver must verify work performed.

Question:

Are new stainless steel H2.5 s required or can the old ones be reused? And will new stainless steel H2.5 s be required on both sides of the “clamp boards”?

Answer:

New H2.5 s be required. Only on one side of the “clamp board” per stringer will require an H2.5 in stainless steel installed with stainless steel screws.

Question:

What does “Bid option: structural piles to be epoxied” mean?

Answer:

It is in relation to the last item listed in the Scope of Work, Substructure, to install FX 763 Epoxy by Denso to top of piles specified to fill all voids and top coated with Archco 15 Acrylic by Denso, requesting a price for an additional 5 post/pile cap to be possibly epoxied. [See Addendum 01 for an updated Bid Sheet that offers clarification.](#)

Question:

Are all piles to be wrapped?

Answer:

No. There are 30 piles drawn within the plans. Of those 30, a total of 4 are to be bid as receiving a structural jacket with the remaining receiving the non structural jackets (or wrap) in the “Base Bid Lump Sum”. The option is requesting the 26 non structural jackets be deleted and upgraded to a structural jacket. This will be added to the Addendum 01 for clarification.

Question:

What type of composite decking is desired as the option for the decking and rail cap?

Answer:

<https://www.moistureshield.com/products/composite-decking/vision/> In the cool deck line colored in Cathedral Stone.

Question:

Should the X Bracing be reinstalled at the proper 45 degree angle or as close as possible or installed in the existing locations and angles? How is the X bracing to be installed in conjunction with the Denso jackets?

Answer:

X bracing should be installed as close as possible to the standard practise of 45 degrees. All should be installed on the piles per the jacket manufacturer’s instructions. This will be added to Addendum 01 for clarification.

Question:

Do all for the intermediate posts need to be replaced and blocked as per the drawing at 3/S4.1?

Answer:

Yes. And all blocking should be installed using stainless steel screws.

Question:

Is it required to use all Denso products? Can Shoreline products be used as an alternate product?

Answer:

If proven to be an equivalent or greater than Denso.

Question:

Where are materials to be staged?

Answer:

There is a grass parking lot that is behind the restroom at Bay Creek Park. The contractor will be responsible for securing the area to prevent the general public from entering or tampering with materials or equipment.

Question:

Any work to be done on the floating dock?

Answer:

Yes the floating dock will need to be re-decked, new band boards, and new bumper rails. Condition of the substructure is unknown. This will be added to Addendum 01 with additional information.